



## **Installation – Guide & What to Expect From Us!**

1. Preparation of quote – either onsite visit or from site/landscape plans provided.
2. Negotiation stage and client acceptance of quotation.
3. Payment of deposit and signing of cash sale and/or account forms.
4. Anticipated start date confirmed by us.
5. Final layout and design to be discussed and agreed – onsite.
6. Job commencement – site preparation works by client or us. (All areas to be minimum thickness of 100mm, with exception of pedestrian limestone areas at 70mm).
7. Installation of formwork defining proposed placement areas. (Mesh installed, if required).
8. Concrete delivery from supplier and placed accordingly.
9. Exposed aggregate concrete areas applied with chemical set retarder and left for following day. Upon return, concrete exposure process completed, with the exception of limestone texture and pattern which is applied the same day.
10. Control joints marked and cut – next day.
11. Acid washing, cleaning in preparation of sealing. (Once dry – weather permitting).
12. Final application of sealing to all areas.

Recommended traffic times :

- a. No foot traffic to any areas within 24 hours of placement.
- b. No vehicle traffic (cars) for 7-10 days from original placement date.
- c. Upon sealing, area to be kept clear without any traffic for a minimum period of 48 hours.

SDii Group Pty Ltd standard terms and conditions of sale to apply.

Also please refer to our Frequently Asked Questions document.